

**Town of Woodbury, Connecticut
Request for Quotation**

**Hollow Park
Field #3 Refurbishment**

Proposals Due: October 1, 2024 @ 10:30 a.m.

REQUEST FOR QUOTATION

The Town of Woodbury, AA/EOE/Title VI, is seeking proposals for a refurbishment of Baseball Field #3 at Hollow Park, including laser grading for drainage, new sod installment, and new clay/conditioner.

Questions may be directed to Mike Lodice, Superintendent of Parks, at (203) 695-4329. Arrangements to view the field prior to bidding can also be made through Mike.

The Town may accept the bid, which in its sole discretion, it determines to be in its own best interest, or it may reject any or all bids. These bidding documents in no way establish the right of the bidder to the award of the contract.

The Town of Woodbury is an Affirmative Action/Equal Opportunity Employee.

Bids must be received in the Selectman's Office, 281 Main Street South, Woodbury, CT 06798, by **10:30 AM, Monday, October 1, 2024**. Please address envelope to: Town of Woodbury, Selectman's Office, 281 Main Street South, CT 06798. Please mark the envelope, "**Hollow Park Field #3.**"



September 23, 2024

Barbara Perkinson
First Selectman

Date

Attachment – Specifications

General Specifications:

RFQ – Hollow Park Field Three Refurbishment

The Town of Woodbury, AA/EOE/Title VI, is seeking proposals for a refurbishment of Baseball Field 3 at Hollow Park including laser grading for drainage, new sod installment and reconstruction of pitcher's mound.

The Contractor shall include the following in their bid:

- Strip existing grass totaling (+/-) 6,700 square feet from infield, 4 feet along basepaths and 4-6 feet around arc of infield transition areas. Haul to onsite designated location at Hollow Park.
- Remove infield lips and provide topsoil to fill depressions and lift grade of infield grass area.
- Laser grade 22 ton of Contractor provided Dura Edge to achieve +/- .5% to promote sheet drainage of water on infield skin.
- Restore infield, base panels, and outfield crescent with Bluegrass sod.
- Rebuild pitcher's mound to proper specifications.
- Reset bases, home plate and pitcher's plate to proper dimensions.
- Estimate of timeframe to complete work
- Confirm availability to complete project this year weather permitting.
- Reference(s) for similar field work completion in the past two years.

If you wish to visit the site before providing a bid, please contact **Mike Lodice, Superintendent of Parks, at (203) 695-4329.**